

**CITY OF FORT SMITH SUPPLEMENTAL SPECIFICATION
CONCRETE CURB AND GUTTER**

SECTION 410 of the Standard Specifications for Public Works Construction, February 2008 Edition, is hereby amended as follows:

410.02 MATERIALS

The first sentence of Item A. CONCRETE shall be deleted and replaced with the following:

Concrete for Types "A" and "B" curb and/or curb and gutter shall be Class "AA" (3500 psi) air entrained, fiber reinforced, as specified in Section 401 "Concrete General" of the specifications.

The following sentence shall be added to Item A. CONCRETE:

Concrete for integral curb shall be same as mix for associated concrete paving.

410.03 CONSTRUCTION REQUIREMENTS

The following Item shall be added to this subsection:

- H. **DRIVEWAYS.** The Contractor may remove no more than two feet of a driveway behind the back of curb in order to remove and replace the gutter across a driveway. A temporary asphalt concrete driveway shall be installed in accordance with section 120.02 CONSTRUCTION REQUIREMENTS, Item F. **PROJECTS ON EXISTING ROADWAYS.** If more than two feet of the driveway is to be replaced, the Contractor may remove the additional length of driveway if it will be replaced with a permanent surface within 24 hours.